

**CITY OF MIDDLETOWN
PURCHASING DEPARTMENT**

ADDENDUM #1 TO BID #2013-014

**Infrastructure Improvements – Birchwood Area Subdivision
Middletown, CT**

Date Issued: May 30, 2013

ALL BIDDERS ARE HEREBY ADVISED OF THE FOLLOWING AMENDMENTS TO THE CONTRACT BID DOCUMENTS:

THE BID HAS BEEN MODIFIED IN THE FOLLOWING AREAS:

**BID DOCUMENT REVISIONS
TECHNICAL SPECIFICATIONS
CONTRACT DRAWINGS**

INVITATION TO BID

The date set for the receipt of proposals will remain the same.

*****Thursday, June 6, 2013 at 11:00 AM*****

PLEASE VERIFY THAT YOU HAVE RECEIVED THIS NOTIFICATION IN THE SPACE BELOW AND FAX OR EMAIL THIS PAGE BACK TO THE PURCHASING DEPARTMENT.

FAX: 860-638-1995

EMAIL: purchase@middletownct.gov

BIDDER ACKNOWLEDGES RECEIPT OF ADDENDUM #1: _____

COMPANY NAME

All bidders are hereby advised of the following amendments to the contract bid documents which are hereby made an integral part of the specifications for the subject project, prepared by the City of Middletown to the same extent as all other documents. All work shall conform to the standards and provisions of same. Bids submitted shall be deemed to include contract document information as shown in Addendum No. 1. General bidders shall notify sub-bidders that may be affected by this addendum as applicable. **Bidders shall be required to acknowledge receipt of this addendum in the space provided on the Bid Proposal Form on Pg. 34.**

Failure to acknowledge receipt of this addendum by the bidder may result in the rejection of their bid. Bidders are directed to review changes to all portions of the work as changes to one portion may affect the work of another.

TOTAL ADDENDA 3 PAGES

*****BIDDER NOTE:** If you have already submitted a bid you shall be required to acknowledge receipt of this addendum under separate cover in a sealed envelope clearly marked with the bid number and description. This acknowledgment must be received by the time and date specified to be accepted by the City

Donna L. Imme, CPPB

ADDENDUM NO. 1

**INFRASTRUCTURE IMPROVEMENTS – BIRCHWOOD AREA SUBDIVISION
MIDDLETOWN, CONNECTICUT
BID NO. 2013-014**

MAY 31, 2013

Public Works Department and Water and Sewer Department

ITEM 1 PRE-BID CONFERENCE

The Pre-Bid Conference Report of Meeting Minutes were issued via the City of Middletown web site and shall become a part of the Contract Documents, including any changes/clarifications to the work included therein. Responses to the Prospective Bidder questions made during the Pre-Bid Conference are included in the Report of Meeting.

ITEM 2 BID DOCUMENT REVISIONS

The following Bid Document pages have been revised and are included in this Addendum. The revised pages are to be added to the Contract as a substitution for the original bid pages and utilized to prepare the final Bid:

Bid Proposal Page 4 dated 05/28/2013. The quantity for Bid Item 1 has changed.

ITEM 3 TECHNICAL SPECIFICATIONS

The following Sections of the Technical Specifications have been modified as follows:

Technical Specification Page 700-8 dated 05/28/2013. Item II-11 3" Concrete Mud Mat has changed. A copy of that page is included in Addendum No. 1.

Section 613 Controlled Low Strength Material shall be removed from the Contract Documents.

ITEM 4 CONTRACT DRAWINGS

The following change shall be made to the referenced drawings:

On Drawing MDS-07 (Sheet 41), under TYPICAL TRENCH CROSS-SECTION (WATER OR FIRE SERVICE), the note, "3" CLSM MUD MAT", shall be changed to read: "3" (3,000 psi concrete Class A) MUD MAT". The use of CLSM shall be replaced with 3,000 psi Class A concrete.

In the bid items that follow, Bidder shall include all applicable taxes, fees and other incidental costs. Bidder must bid on every item. Prices are to be written in words and figures. In case of a discrepancy, the bid amount in words shall prevail.

#	Item # with spec. ref	QTY.	UNIT OF MEASURE	ITEM DESCRIPTION UNIT PRICE WORDS AND FIGURES	EXTENSION IN FIGURES
ROADWAY IMPROVEMENTS					
1	I-2 102 104	19,000*	CUBIC YARD	CLEARING & GRUBBING/EXCAVATION FOR SURFACE IMPROVEMENTS (\$) WRITTEN FIGURES	\$
2	I-3 102	1,000	CUBIC YARD	UNSUITABLE MATERIAL EXCAVATION BELOW NORMAL GRADE (\$) WRITTEN FIGURES	\$
3	II-1 301	5,000	CUBIC YARD	PROCESSED AGGREGATE BASE (\$) WRITTEN FIGURES	\$
4	II-2 109	20,000	SQUARE YARD	FORMATION OF SUBGRADE (\$) WRITTEN FIGURES	\$
5	II-3 106A	250	CUBIC YARD	NO. 8 CRUSHED STONE (\$) WRITTEN FIGURES	\$
6	II-4 401	2,250	PER TON	2" BITUMINOUS CONCRETE, CLASS 1 (\$) WRITTEN FIGURES	\$
7	II-5 401	2,250	PER TON	2" BITUMINOUS CONCRETE, CLASS 2 (\$) WRITTEN FIGURES	\$

* Revised by Addendum No. 1 5/31/2013



ITEM II-11 3" CONCRETE MUD MAT*

- (a) The placement of this Item will be measured for payment based upon the actual square footage of 3" thickness "mud mat" placed on undisturbed subgrade below pipes and/or structures as detailed on the Drawings or as directed by the Engineer. The placement measured for payment shall not exceed the trench or structure excavation limits stated in the specifications, unless otherwise approved by the Engineer.
- (b) This work shall be paid for at the Contract unit price per square foot of "3" Mud Mat", complete in place to the maximum trench/excavation limits allowed by the specifications/details, which price shall include furnishing and placing the 3,000 psi concrete (Class A), and all other materials, tools, equipment and labor incidental thereto.

ITEM II-12 ROADWAY SUBBASE

- (a) Roadway Subbase for providing a stable subbase between the processed aggregate base and the subgrade material shall be measured for payment based upon the actual number of cubic yards furnished, placed and compacted within the limits defined by the details or as determined by the Engineer. Roadway Subbase shall conform to Section 107 of these Specifications.
- (b) This work will be paid for at the Contract unit price per cubic yard for "Roadway Subbase", complete in place, which price shall include all materials, tools, equipment and labor incidental thereto.

ITEM II-13 RIPRAP

- (a) This work will be measured for payment by the actual number of square yards of modified riprap placed on a prepared base to the thickness detailed and accepted.
- (b) The unit price for this Item shall be full compensation for clearing and grubbing, earth excavation, furnishing and installing the granular base material and modified riprap to the thicknesses detailed and to the limits shown on the drawings, or as directed by the Engineer, grading and compaction, disposal of surplus material, and all labor, materials, tools and equipment necessary to complete the Item to the satisfaction of the Engineer.

III. INCIDENTAL WORK

ITEM III-1 6" UNDERDRAIN

- (a) This work will be measured for payment by the actual number of linear feet of underdrains, foundation underdrains, slope underdrains, structural underdrains and outlets for underdrains, completed, accepted and measured in place. Trench excavation will not be measured for payment. Rock-in-trench will be measured for payment in accordance with Item I-1.
- (b) This work will be paid for at the Contract unit price per linear foot for "6" Underdrain", complete in place, which price shall include pipe of the size specified, elbows, tees, wyes, couplings, fitting, trench excavation and support, geotextile, furnishing and placing No. 8 crushed stone, aggregate, sand, backfill and compaction, and equipment, tools, material and labor incidental thereto.